



- PAVEMENT SPECIFICATIONS:**
- 1 1/2" TYPE S-1 ASPHALTIC CONCRETE SURFACE COURSE, 1500 P.S.I. MARSHALL STABILITY TEST
 - 6" LIMEROCK OR CEMENTED COQUINA ROCK BASE COMPACTED TO 98% AASHTO T-180, L.B.R. 100 MINIMUM WITH PRIME COAT (8" BASE ON PROPOSED COUNTY-MAINTAINED SEGMENT OF CASABELLA PLACE)
 - 8" STABILIZED SUBBASE, MIXED WITH 4" LIMEROCK OR CRUSHED COQUINA COMPACTED TO 98% AASHTO T-180, L.B.R. 50 MINIMUM
 - SIDEWALKS: 4" THICK, 3,000 P.S.I. CONCRETE; TO BE 6" THICK, 3,000 P.S.I. CONCRETE SIDEWALKS SHALL HAVE SAW CUT CONTROL JOINTS AT 5' CENTERS. PROVIDE 6" X 6" No. 10/10 W.W.F. REINFORCEMENT AT DRIVEWAYS. SIDEWALK ALONG WICKHAM ROAD TO BE 6" THICK WITH FIBERMESH REINFORCEMENT.
- GRASS SPECIFICATIONS:**
- CONTRACTOR SHALL SEED AND MULCH ALL UNPAVED AREAS WITHIN THE RIGHT OF WAY.
 - CONTRACTOR SHALL SOD 2' BEHIND BACK OF CURB.
 - CONTRACTOR TO SOD ALL SLOPES > 5:1.
 - CONTRACTOR TO SEED & MULCH LAKE BANKS (WITH SOD ALTERNATE, OWNER OPTION)

LEE ENGINEERING, INC.
 105 N. Palm Avenue
 Indianton, Florida 32903
 (321) 793-7110
 FBPE CERTIFICATE OF AUTHORIZATION #5969

Casabella
 CROSS SECTIONS for
 STREETS and LOTS

STATUS	DATE
P	PRELIMINARY
A	ISSUED FOR APPROVALS
B	BOOKING ONLY
RC	RELEASED FOR CONSTRUCTION
RD	RECORDS Dwg
CK	CHECK PRINT

JOB No.: 0152-1
 FILE: XSEC-revswk
 BORDER: N/A
 VP-1: N/A
 VP-2: N/A
 VP-3: N/A
 VP-4: N/A
 VP-5: N/A
 VP-6: N/A
 VP-7: N/A
 VP-8: N/A
 DATE: 09-01-98
 SCALE: NOTED
16 of 21
 ENGINEER OF RECORD
 FL PE # 41077

APPROVED FOR
 PHASE ONE ONLY!